



Ministry of Finance

**Upgrading of Adh.Fenfushi Harbour**

**TES/2020/W-021**

**Clarification 1**

Question	Answers
How to handle with the excavated sea sand? whether the owner will provide a specific disposal location for the excavated sea sand?	Dredge material will be used mainly to back fill and to reclamation if there is any reclamation area shown in layout. Any excess dredge material will be stock pile. Stock pile location will not be any area far away from harbour site. This area will be decided during the community consultation period in EIA stage. This stage will be done by the winning contractor.
Is the Contractor responsible for applying for approvals or permits from the government regarding the project? If so, what kind of approvals or permits need to be obtained before the commencement of the project?	Once the project is awarded the only permit that need is access to site. This will be done from Ministry side. The winning contractor has to inform ministry the area they required for site setup. EIA will be done from Ministries side. SO when the awarding contractor is mobilized all permits required will be there to commence work.
What kind of surveys need to done by the Contractor?	The winning contractor has to do a detailed in survey including a bathymetry of the harbor area before commencing work and also has to establish a PSM point according to MLSA regulation.
As per the section - 5 Scope of works - Design criteria (Point 2&3) specifies the sediment movement in to the harbor basin	There is no data to this matter at the moment. Our suggestion is to use core in any breakwater/groaned that needs to be constructed. As EIA process is done by ministry we will inform the bidders if any design change is required. Otherwise proceed with the current design with breakwater and groaned with a core.
The data on littoral drift with under water current study covering the seasons are necessary for orienting the entry channel	there is no need for this in this project. Fenfushi has an existing channel and we are not proposing any change to this.
The Provisional sum for the dismantling of existing breakwater & quay wall is not specified in the BOQ, can we include the costing details in additions. Kindly advice.	Revised BOQ will have in additions the demolition of existing quay wall/breakwater
Extension of time: the data collection may be involved, we request you to consider the extension of the tender for further - 15 days for the same.	Time extensions will be given accordingly. Ministry will extend after studying the situation and if its necessary.

