


DOOR WINDOW SCHEDULE - SH.LHAIMAGU HEALTH CENTE RENOVATION

1.50

D1	
	
LOCATION	PUBLIC TOILET
QUANTITY	01
FRAME	TREATED SOLID TIMBER
PANEL	TREATED SOLID TIMBER (READY MADE-DOOR PANEL)
FINISH	SEAMASTER/SIGMA OR EQUIVALENT ENAMEL PAINT
HINGE	SS HINGES SINGLE SIDE OPENING
LOCK	STATE MAKE (CYLINDRICAL TOILET LOCK)
NOTE	ALL MEASUREMENTS TO BE CHECKED ON SITE

ALL MEASUREMENTS TO BE CHECKED ON SITE BEFORE FABRICATION

FG = FIXED 5MM FROSTED GLASS