



NOTES:-

1. THESE DRAWINGS ARE PRELIMINARY AND ARE FOR TENDERING PURPOSES ONLY.

2. CONTRACTOR SHALL CARRY OUT DETAILED SITE SURVEY AND ENGINEERING / STUDY TO EVALUATE AND PROPOSE THE EXTENT OF REPLACEMENT / MODIFICATION REQUIRED IN THE EXISTING DISTRIBUTION NETWORK. THIS IS SUBJECT TO REVIEW AND APPROVAL BY THE EMPLOYER DURING THE ENGINEERING PHASE OF THE PROJECT.

LEGEND:-		
SYMBOL	DESCRIPTION	QUANTITY
-----	PROPOSED 300sq.mm Cu/XLPE/SWA/PVC/PVC Cable 410m	

PURPOSE OF SUBMISSION		REV	AUTHORISED BY	DATE	DRAWING TITLE CONCEPTUAL SCHEMATIC DIAGRAM FOR LV DISTRIBUTION BOARD OF POWER HOUSE (B12-KULHUDHUFFUSHI)	DESIGN : ESM	SCALE : N.T.S
INITIAL DOCUMENTS		A	GKH	28/03/16		DRAWN : DAI/MBA	DRW NO. : J431-GOPA-032-GR-E-S-0001-RevD
FIRST REVISION		B	GKH	25/05/16	PROJECT PREPARING OUTER ISLANDS SUSTAINABLE DEVELOPMENT	CLIENT: GOVERNMENT OF THE REPUBLIC OF MALDIVES	ISLAND NAME : KULHUDHUFFUSHI
SECOND REVISION		C	GKH	19/06/16			
THIRD REVISION		D	SWK	04/08/16			
						LICENCE NO:	
						DATE: : 04AUG16	PAGE : 1/2

KULHUDHUFFUSHI-POWER HOUSE-PROPOSED PV FEEDER

From	To	No. of Runs	Cable Size (sq.mm)	Length (M)	Cable Current Capacity (A)	Cable Current Capacity After Deration (0.6) (A)	Power (kW)	Current (A)	Cable Loading (%)	Voltage (%) at DB Main Bus	Total Voltage Drop (%) in Cable Section	% Voltage Drop upto Distribution Boards	% Voltage Drop Acceptable (Less Than 5%)	Losses (%)	Remarks
AFEEFUDIN SCHOOL-PV	KULHUDHUFFUSHI-POWER HOUSE	1	4C x 300	410	590	354	139	195.5	55.2	102.62	2.62	2.62	YES	2.59%	Proposed 4C x 300 sq.mm LV Cable

	PURPOSE OF SUBMISSION	REV	AUTHORISED BY	DATE				
	INITIAL DOCUMENTS	A	GKH	28/03/16	DRAWING TITLE CONCEPTUAL SCHEMATIC DIAGRAM FOR LV DISTRIBUTION BOARD OF POWER HOUSE (B12-KULHUDHUFFUSHI)		DESIGN : ESM	SCALE : N.T.S
	FIRST REVISION	B	GKH	25/05/16			DRAWN : DAI/MBA	DRW NO. : J431-G0PA-032-GR-E-S-0001-RevD
	SECOND REVISION	C	GKH	19/06/16	PROJECT PREPARING OUTER ISLANDS SUSTAINABLE DEVELOPMENT	CLIENT: GOVERNMENT OF THE REPUBLIC OF MALDIVES	LICENCE NO:	ISLAND NAME : KULHUDHUFFUSHI
	THIRD REVISION	D	SWK	04/08/16			DATE: : 04AUG16	PAGE : 2/2