

بِسْمِ اللَّهِ الرَّحْمَنِ الرَّحِيمِ



**Ministry of Sports, Fitness and Recreation
Republic of Maldives**

07th April 2026

**Project Scope Statement for HA.Kelaa Football Ground (Preparation of
subbase, Boundary wall & fence, Lighting System and Turf Supply &
Installation)**

The aim of developing the turf football ground is to provide a dedicated space for youth engagement in sports, thereby promoting a healthy and active lifestyle.

The contractor needs to arrange temporary water and electricity to the site if needed. The site has no building/trees to be cleared or demolished.

The main scope for this project comprises of all Architectural drawings, BOQ and Specifications provided.

The scope of this project includes:

Subbase

- Excavation, backfilling, Levelling & Compaction
- Concrete work
- Paving Work
- Plumbing Work

Boundary wall and fence

- Concrete works
- Masonry and Plastering.
- Fencing works
- Painting

Lighting System

- Prepare light pole footing (according to BOQ and Drawings).
- Supplying and installation 8 lighting poles including 1000w 4 LED flood lights on each pole. (according to BOQ and Drawings)
- Electrical wiring and connecting the switches as mentioned in BOQ.

Turf supply and installation

- Supplying and installation of turf, Infilling silica sand and rubber granules (according to BOQ)
- Installation of goal post as mentioned in BOQ (including goal net)
- Installation of corner flag as per mentioned in BOQ.
- Supply and delivery of Drag Brush Machine.

Note: Please submit samples (as required in the BOQ) of turf, silica sand, and rubber granules for material approval along with the bid submission. Bids that do not meet our sample requirements will be disqualified.