



اسم اللہ العزیز



**Ministry of Finance**  
Male', Republic of Maldives

<b>Contractor Comments</b>	<b>Response/Reference Document</b>
BOQ Item no: 11.2, there are two main Panel boards, 1 single phase unit and 1 three phase unit. Kindly clarify if those two are required?	Those DBs are required (essential) and it's not a single-phase DB. It has 8 nos of single-phase DBs for each shop.
Main cable is not included in BOQ. If main cable to be included, what is the length?	Lengths will be as follows, from MDB to DB1 - 8m from MDB to DB2 - 16m from MDB to DB3 - 20m from MDB to DB4 - 25m from MDB to DB5 - 8m from MDB to DB6 - 15m from MDB to DB7 - 16m from MDB to DB8 - 21m

*AM*



*[Handwritten signature]*