



Ministry of Finance

Ameenee Magu, Male', Republic of Maldives

Telephone: (960) 334 9266, Fax: (960) 332 0706

ދިވެހިސަރުކާރުގެ ގެޒެޓް
ރާއްޖޭގެ ބޭރުގެ ގަވާއިދު

CLARIFICATION 1

1 ވަނަ ބަޔާންކުރުމުގެ ބަޔާން

ނަންބަރު No:	TES/2020/W-044-R01	
ފްރޮޕްޖެކްޓް Project:	Construction of B.Eydhafushi Atoll Hospital Extension under Contractor Finance	
އިއްޔާކުރުމުގެ ތާރީޚު Issued Date	19 th November 2020	
ސަފުހާގެ އަދަދު No. of Pages: -03	ބޯޖު Boq: -00	ޖަހާފައިވާ ވަނަވަންތަ Drawings: -00

އަދި ބަޔާންކުރުމުގެ ބަޔާން ހުށަހަޅާ ފަހަރު މި ބަޔާންކުރުމުގެ ބަޔާން ހިމާލައިގެން ހުށަހަޅާން ބޭނުންވާނެއެވެ. Please include this clarification when submitting the bid.

Attached with, please find;

- Answers to the queries raised.



ނަންބަރު

Name: Fathimath Rishfa Ahmed

ސަފްޞާ

Signature:

Find the below answers to the queries raised with regard to the project.

1. The lift details provided in the BOQ specifies that it requires to access for the floors whereas the requirement for no. of floors is not provided, kindly confirm.
[Refer to the drawings.](#)
2. As it a special building the electrical routing shall be specified according to the Bio - medical equipment's specific requirement.
[Electrical requirement of dedicated areas shall be considered and valued.](#)
[eg: Laboratory area, CSSD, X-ray room.](#)
3. The electrical Main board's details should be given with proper specification like the type of board, circuit breakers, MCB and main DB, No of incomer & outgoing cables.
[Include in Contractors scope of work. Electric design and MEA approval shall be provided by Contractor.](#)
4. The transformer details are not provided in the BOQ, is there any requirement for the building.
[Electrical design shall include such requirement with design and installation.](#)
5. The genset requirement is not provided and if required, the capacity details and the type of genset and the main board distribution details to be specified.
[Backup generator required to operate all servicing areas excluding administrative units.](#)
6. The oxygen and Air for all beds is provided in the BOQ, we request you to provide the layout for the same.
[Requirement provided in MEP drawings, layout design, shop drawings part of Contractors scope.](#)
7. The sewer connection to the main line is provided in Item; kindly specify the details of sewer connection that has to be provided.
[Connection and piping works shall be as per the design specification and complying to utility guidelines.](#)
8. For quoting the CCTV, the storage capacity is not provided; Does the backup required and the functioning of CCTV shall be connected with inverter for continuous operation.
[For storage, please consider CCTV Backup for up to 5 months duration.](#)
9. EPBX and the paging system facilities are required, Please clarify.
[Refer provided service requirement.](#)
10. Freezer provision for the blood bank and the organ donations has not incorporated in the details of the technical specification, please clarify.
[Provisions shall be provided as per the electrical requirement of dedicated areas.](#)
[See item 2.](#)

11. Since it's a hospital building any special treatment, cobalt room, surgical room are required.
[Provisions given in original design.](#)
12. Only the bed curtains are design and supply has been provided in the BOQ, does the rate shall include the Beds, Cot and the bed spreads?
[Medical grade bed curtain only. Beds, cot and bed spread not required.](#)
13. The Elevation details for the reception is included with the interior designing, but there is no such BOQ details provide. Do we need to provide the costing for the same? Kindly clarify
[Refer boq item 6.3](#)
[Interior decorations shall be read in conjunction with drawings, boq and 3d render designs.](#)
14. Is there provision for the water tank the capacity details shall be provided for calculating the water source for the firefighting and the plumbing connections?
[Water tank for firefighting not required. Please refer service drawings.](#)
15. The hospital waste disposal plan is not specified.
[To be Included as Contractors scope of work. Dedicated waste disposal area required.](#)
16. The terrace water proofing details are not specified in the BOQ details
[Can opt a method of similar work in other areas.](#)
17. The elevation features are to be detailed in the BOQ as per the drawing
[Interior and exterior decorations shall be read in conjunction with drawings, boq and 3d render designs.](#)
18. Kindly provide the stipulated time for project completion
[18 Months](#)
19. Please confirm that which ministry will sign the final contract with the financial institution.
[It is the responsibility of the bidder to raise funds for the project. Bidder should submit Proposed Repayment Plan along with the bid. Once contract is entered, payment to the contractor will be made as per the proposed repayment plan.](#)
20. Contractor Finance payment term : Please clarify that in case of the contractor finance what is the other guarantee will be provided in lieu of the sovereign guarantee.
[No guarantees to be provided by the Government of Maldives.](#)