







SCHEDULE OF SPECIALS AND FITTINGS

ITEM	SPECIALS AND FITTINGS	QTY
1	DI - SPIGOT PIPE WITH WELDED THRUST FLANGE	1
2	FLOW METER	1
3	FLANGED ADAPTOR	1
4	DI FLANGED-SPIGOT PIECE	1
5	DI/PE ADAPTOR	2
6	DI FLANGED SPIGOT PIPE WITH WELDED PUDDLE FLANGE	1
7	DI SHORT LENGTH FLANGED SPIGOT PIECE	2
8	DI COLLAR	2

DIMENSIONS OF VALVE CHAMBER

Dia of Pipe (d)	L	B	a
80-200	1200	1200	250
250	1450	1250	425
300	1750	1300	650
350	2000	1350	875
400	2300	1400	1100
450	2500	1450	1325
500	2850	1500	1575



NOTES:

- All dimensions are in mm
- For location and depths of Gate valve chamber refer to drawings of pipeline plans and profiles.
- The specials and pipe fittings shall be selected to suit the supply pipe line
- All the valves, specials and pipes inside the chamber should be of Ductile iron
- Flow meter shall comply with BS 5150
- DI pipe & Fitting shall comply with BS 4772
- Building materials:-
Description of building materials is as follows
Compressive strength of concrete \uparrow Sulphate resistant cement
maximum size of aggregate \uparrow

ABBREVIATIONS

PIL - PIPE INVERT LEVEL.
MS - MILD STEEL.
DI - DUCTILE IRON.
PE - POLY ETHYLENE
RCC - REINFORCED CEMENT CONCRETE
PCC - PLAIN CEMENT CONCRETE

- Concrete:
a. mixes shall comply with BS 8110
b. minimum 28 day characteristic strength in accordance with BS 8110
- Cover to reinforcement to be 50mm.
- The steel used shall be of fy 350 grade.
- The tanking shall be with two layers of Bituminous Paint for external surfaces of Valve chamber
- Gate Valve Chamber to be provided for Pipe dia 200 to 300 mm
- MH Cover Should Comply to BS EN 124 Class D4.00

No.	DATE	DESCRIPTION	DRG. No.	DESCRIPTION
		REVISION	REFERENCE DRAWINGS	

CLIENT
MINISTRY OF ENVIRONMENT AND ENERGY
MALE REPUBLIC OF MALDIVES

PROJECT
CONSULTANCY SERVICES FOR SURVEY, DESIGN OF WATER SUPPLY FACILITIES IN THE ISLAND SH. FOAKAIDHOO, MALDIVES

TITLE
TYPICAL DRAWING OF BULK FLOW METER CHAMBER

DESIGNED BY
SHAH TECHNICAL CONSULTANTS PVT. LTD., INDIA
In Association With
DEVELOPMENT TECHNOLOGIES MALDIVES, MALDIVES

APPROVED	CHECKED	DESIGNED	DRAWN
SSS	SSS	RKC	SSN

SCALE: AS SHOWN
DATE: NOV 2017
DRAWING No.: Sh. Foakaidhoo/WS/07
REVISION: 0