



CLARIFICATION 1

ފުޅުބޭނުންކުރާ ދާއިރާގެ ޖުމްހޫރިއްޔާގެ ސަރުކާރުގެ ތެރެއިން

ނަންބަރު No:	TES/2025/W-101	
ޕްރޮޖެކްޓް Project:	Construction of a state-of-the-art TVET Center at Fuvahmulah City	
ޖުމްހޫރިއްޔާ Issued Date	11 th September 2025	
ސަފުހާގެ ޖުމްހޫރިއްޔާ No. of Pages: -02	ބޯޕްޕްޔާ BoQ: -00	ޖަހާފައިވާ ޖުމްހޫރިއްޔާ Drawings: -00


Please include this sheet when submitting the bid

މި ޖަހާފައިވާ ޖުމްހޫރިއްޔާ ގައި ބަޔާންކުރި ޖުމްހޫރިއްޔާގެ ތެރެއިން ޖަހާފައިވާ ޖުމްހޫރިއްޔާގެ ތެރެއިން

➤ Please find below the response to the queries raised.

Queries	Response/Reference Document
1. Door and windows specification glass thickness mentioned in BOQ is not commonly used thickness glass. Please let us know how we can proceed. (if we go BOQ thickness, later some damages happen, it's difficult to change the glass)	A revised BOQ has been issued (Refer to addendum 2) Following BOQ Items in Bill F (Doors & Windows) to change the thickness of the glass from 9mm to 12mm, Item 1, 3, 9, 23, 24, 30, 31, 32, 33. Additionally (apart from the inquiry), some of the missing items were added to BOQ Bill F, Item 37, 38 and 39.
2. Furniture specification, sound system and projector not in BOQ. (how we need to proceed)	A revised BOQ has been issued (Refer to addendum 2) inclusive of the items (BOQ Bill O, under Second Floor/Auditorium).
3. Omission and Addition Omission and Addition Bill not included in the BOQ We have noticed that some items indicated in the drawings are not included in the BOQ. In this regard, we kindly request clarification on how such items should be treated, especially since an addition and omission sheet is not provided, and considering that the Letter of Tender specifies a lump-sum fixed price basis.	A revised BOQ has been issued (Refer to addendum 2) with Additions and Omissions has been provided. Bidders are instructed to include any such items in these sections of the BOQ (BOQ Bill R and S).
4. Bill No: 03 CONCRETE WORK Ramp & Steps concrete work The ramp and steps shown in Tender drawing no. AR02 are not included in the Bill of Quantities (BOQ) - Please Clarify	A revised BOQ has been issued (Refer to addendum 2) inclusive of the Building Entrance and Workshop Entrance Ramp (BOQ Bill Q, Item 8 and 9).
5. Others Concrete work Lintel and Sill beam concrete work Not included in the BOQ - Please Clarify	Concrete beams should be provided horizontally beneath all external walls, middle of all masonry walls and above all windows and doors. These costs should be included into the masonry wall section of the BOQ (BOQ Bill D).

<p>6.Bill No: 09 ROOFING WORKS</p> <p>Roofing sheet Framing work materials</p> <p>In BOQ Bill No. 9.1, the specification states “zinc aluminum roofing sheets on timber framework consisting of 50x150mm timber rafters @600mm c/c, 200x50mm timber ridge support, 50x50mm timber battens @100mm c/c, 100x150mm timber wall plate, 12mm anchor bolt, etc. as per the detail drawings.”</p> <p>However, the detail drawings provided indicate a steel-framed truss system instead of a timber framework. Please Clarify</p>	<p>A revised BOQ has been issued (Refer to addendum 2) changing the roof system as in the provided drawings. Bidders are instructed to submit prices as per the drawing. (BOQ Bill I, Item 1).</p>
<p>7. Security Check Point</p>	<p>A revised BOQ has been issued (Refer to addendum 2) inclusive of the Security Check Point (BOQ Bill Q, Item 10).</p>


Name: Aminath Naheen Ahmed


Signature:

