



Ministry of Finance

Male', Republic of Maldives

Construction of Proposed 08 Classroom and Multi-purpose hall at M.Kolhufushi School

TES2019W-141

Clarification 1

Contractor Comments	Ministry of Education Response/Reference Document
1. Please provide details of demolition and cutting of trees?	Headmaster house (68ft X 27ft) 2 Store room (33ft x 20ft)
2. Is EIA done for this project or do we need to make one by ourselves?	If previous EIA done, information to be given by School/MOE. Do not need make one for this project.
3. Where to dump construction debris?	5 min drive is required for the specified debris area
4. Can we use local sand for Block making?	Can be used after proper cleaning but prefer river sand after proper cleaning
5. Please clarify the availability of material storage and accommodation	Material storage and accommodation will be available
6. Can we use M-Sand for concrete?	Yes
7. Can we use local sand for block work mortar and plastering?	Use M-Sand for block work mortar Use river sand for plastering
8. Can we use ground water for construction?	Ground water cannot be used for construction
9. Where to get water and electricity?	Fenaka Temporary board available for rent
10. Please provide intended duration and budget of the project	Duration shall be submitted by the contractor
11. Rain water collection required or not?	Rain water collection is required
12. Kindly provide the distance from the waste management site	5 min drive



13. Self levelling screeding mentioned in the drawing, it will be expensive than normal screed, please confirm	Please follow the drawing specifications
14. Stiffener column reinforcement details not given	Stiffener column reinforcement details: 2T12 & R6 @ 150 C/C
15. Kindly provide the distance from the Electrical Main DB	30 FT
16. Kindly provide the distance from the main sewer	200FT

