


	(a) Rates shall include for: cleaning out cavities, forming rebated reveals and pointing and cleaning down to reveals where necessary; fractional size blocks, all necessary machine cutting, cutting or forming chases or edges of		
	floor slabs, cutting or leaving holes and openings as recesses for and building in pipes, conduits, sleeves and similar as required for all trades; leaving surfaces rough or raking out joints for plastering and flashings, bedding		
	frames or plates, building in joists, bearers or similar, temporary supports to openings, templates, reinforcement in walls and for all necessary making good		
4.2	<u>Cement brickwork</u>	Unit	QTY
4.2.1	4" cement solid blocks, laid on and incl. mortar tie rods, compression joint gap filler, nylon/plastic mesh as specified (external walls)		
(1)	Ground floor	m ²	93.00
(2)	First floor	m ²	110.70
4.2.2	4" cement solid blocks, laid on and incl. mortar tie rods, compression joint gap filler, nylon/plastic mesh as specified (internal walls)		
(1)	Ground floor	m ²	6.50
(2)	First floor	m ²	56.00
4.3	<u>Plastering</u>	Unit	QTY
	(a) Cement plastering on walls and concrete surfaces as specified incl. wire mesh at the joints of concrete surfaces and walls		
4.3.1	2x12mm thick (two coats) cement plastering (external surface of walls)		
(1)	Ground floor	m ²	186.00
(2)	First floor	m ²	110.70
4.3.2	15mm thick cement plastering (internal surface of walls)		
(1)	Ground floor	m ²	106.00
(2)	First floor	m ²	222.70
4.4	<u>Cement Screed</u>	Unit	QTY
4.4.1	35 mm thick floor screed on:		



(1)	Ground floor including ramp and steps	m ²	191.00
(2)	First floor	m ²	156.00
(3)	Staircase	m ²	18.00
4.5	<u>Paving</u>	Unit	QTY
4.5.1	Paving blocks		
(1)	Ground	m ²	15.75
4.6	<u>Partition</u>	Unit	QTY
4.6.1	Gypsum board partition including timber framing and all other fixing		
(1)	First floor cafeteria area partition	m ²	22.80

2. What is the size of Floor Tiles and Wall Tiles to be used? Height of wall tiles also to be mentioned.

<u>BILL NO: 08</u>			
<u>TILING</u>			
-			
8.1	<u>General</u>	Unit	QTY
	(a) Rates shall include for: motar, fixing, bedding, grouting, and pointing materials; making good around pipes, sanitary fixtures, and similar; cleaning down and polishing.		
8.2	<u>Floor Tiles</u>		
8.2.1	Ceramic floor tiles (450x450 Non slip)		
(1)	Ground floor fish landing area	m ²	150.00
8.2.2	Ceramic floor tiles (300x300 Non slip)		
(1)	Ground floor ramps including steps	m ²	38.00
8.2.3	Ceramic floor tiles (450x450 Non slip)		
(1)	First floor	m ²	144.00
8.2.4	Ceramic floor tiles (300x300 Non slip)		
(1)	First floor toilet	m ²	13.00
8.2.5	Ceramic floor tiles (300x300 Non slip)		
(1)	Staircase including nosing tile	m ²	18.00
8.3	<u>Wall tiles</u>		
8.3.1	Ceramic wall tiles (200x200 Glazed)		
(1)	Ground floor fish landing area	m ²	94.00
8.3.2	Ceramic wall tiles (200x300 Glazed)		
(1)	First floor toilet	m ²	57.00

3. What is the Paint finish to be given for Inner and Outer walls? Details needed.



BILL No: 9			
<u>PAINING</u>			
9.1	<u>General</u>	Unit	QTY
	(a) Rates shall include for: the provision, erection and removal of scaffolding, preparation, rubbing down between coats and similar work, the protection and/or masking floors, fittings and similar work, removing and replacing door and window		
	(b) All painting work shall be carried in accordance with the Specifications		
	(c) Paint system shall be Dulux or Equivalent		
9.2	<u>Wall painting</u>		
9.2.1	Emulsion paint finish on cement plastered surfaces (external surfaces of walls)		
(1)	Ground floor	m ²	213.90
(2)	First floor	m ²	127.31
9.2.2	Emulsion paint finish on cement plastered surfaces (internal surfaces of walls)		
(1)	Ground floor	m ²	27.90
(2)	First floor	m ²	221.91
9.2.2	Emulsion paint finish on soffits and sides of beams	m ²	182.70

4. We need full detailed BOQ with all specifications and details of work providing us to make a good quote for the above.

Full B.o.Q Details and Technical Specification is Attached

The **Bid Opening** for the project will be held on **Wednesday, 29th March 2017, 11:00hrs** at National tender and project monitoring of Ministry of Finance and Treasury (5th floor, Treasury building)


Name: Ahmed Mujuthaba


Signature:

