

بِسْمِ اللّٰهِ الرَّحْمٰنِ الرَّحِیْمِ



Ministry of Finance
Ameenee Magu, Male', Republic of Maldives
Telephone: (960) 334 9266, Fax: (960) 332 0706

ދިވެހިސަރުކާރުގެ ލިބިގެންވާ
ފަރާތްތަކުގެ ލިބިގެންވާ

CLARIFICATION 1

1 ވަނަ ފުރުހުމުގެ ޖަނުވަތަ

ނަންބަރު No:	Construction of 25 Housing Units at Ha.Dhihdhoo		
މަޢުލޫމާތު Project:	TES/2022/W-075		
ދަތުރު Issued Date	19 th October 2023		
ފަންދުގެ އަދަދު No. of Pages: -03	މަޢުލޫމާތު BoQ: -00	ފަންދުގެ Drawings: -00	

Please include this amendment when submitting the bid. ބަދަލުގެ ޖަނުވަތަ ހިމާލައިގެން ލިބިގެންވާ ފަންދުގެ ޖަނުވަތަ ހިމާލައިގެން ލިބިގެންވާ

➤ **Answers for the queries is attached with this Clarification.**

ނަންބަރު

Name: Aishath Nadheema

ފަންދު

Signature: 





Ministry of Finance
Male', Republic of Maldives

Contractor Comments	Response/Reference Document
<p>1. Distance of Buildings to Road Electrical Distribution Board: Could you please provide information on the distance between the buildings specified in the tender and the nearest road electrical distribution board? This will help us accurately plan for electrical connections.</p>	<p>Distance from the plot to the nearest DB is around 25ft as per council. But this may differ a little.</p>
<p>2. Inclusion of Landscaping Works in BOQ: Should landscaping works be included in the Bill of Quantities (BOQ), or are they to be treated separately? Clarification on this matter will enable us to align our cost estimation accordingly.</p>	<p>Landscaping work is not included in this project</p>
<p>3. Overhead Water Tank in BOQ: Are we required to include the overhead water tank itself in the BOQ, or should we only consider provisions for the tank? If inclusion is necessary, please specify the type of overhead tank to be considered</p>	<p>No overhead water tank is given in the BOQ that we have provided</p>
<p>4. Type of Overhead Tank: If the overhead water tank is to be included in the BOQ, kindly specify the type, capacity, and any specific requirements associated with the tank</p>	<p>No overhead water tank is needed for this project</p>
<p>5. Connectivity Details: Please provide detailed information regarding the connectivity of the project site to main electricity, water supply, sewage systems, telephone lines, and internet connectivity. Understanding these connections is crucial for our planning.</p>	<p>The contractor shall provide connection up to the road DB.</p>



<p>6. 20A Sockets in BOQ: The employer's requirement sheet mentions 20A sockets in the bedrooms, but these are not explicitly listed in the provided BOQ. Should we include 20A sockets in the BOQ?</p>	<p>yes, include 20A sockets in your pricing.</p>
<p>7. Sheet Pile Shoring: Sheet pile shoring is mentioned in the provided drawings. Could you please clarify if sheet pile shoring is required for all areas of the project, or if there are specific locations where it should be implemented?</p>	<p>Sheet pile shoring is not mentioned in drawings as this project does not require it. Please double check to see if it is the drawings we provided.</p>
<p>8. Use of M.Sand for Construction: Could you please confirm if the use of M.Sand (Manufactured Sand) is permissible for construction purposes according to the project specifications?</p>	<p>Contractor can use M Sand for construction</p>



Handwritten signature in blue ink.