



دیرینه پر حق و سترسته رسته
 راجه پرستی، دگر، بدو رستم رستم

3 ٥٥ ١٥٥ ٤٤
 سرع سرع

نمبر سند No:	TES/2018/W-03		
نوع سند Project:	Establishment of a Drainage System - S.Feydhoo		
تاریخ Issued Date	26 th March 2018		
نمبر صفحات No. of Pages: -2	نمبر Boq: -01	نمبر Drawings: -01	

Please include this amendment when submitting the bid. بماتى

- Find the attached Clarification 1
- Revised BOQ and Storm water drawings are enclosed with this amendment

Please be informed that the **bid opening** for the project will be held on **Tuesday, 3rd April 2018, 1000hrs** at Ministry of Finance and Treasury, National Tender's Meeting Room.

اسم: **Aminath Naheen Ahmed**

Signature:

Page 1 of 2



Establishment of a Drainage System - S.Feydhoo

Clarification – 1

1. Please confirm this measuring and pay or Lump sum contract?

Yes it is a Lump sum project as informed in the clarification meeting

2. Please provide details design drawing for sea outfall. BOQ has 200 plus meter pipe and concrete blocks.

The discharge point for outfall ends at quay wall. It is given in bill no.6, gravity flow line.

3. Please give distance between Island power DB to Lifting pumping station, or length of cable and size of cable.

The distance between island power DB to lifting stations are given in Bill no.4.3

4. Please provide pump panel board details, electrical reading meter details

Details of pup panel boards are given in bill no. 4.3. Contractor can propose equipment panel for MEA approval

5. Bio swale-gravel size, Growing medium particle size and Geo textile details not shown in Drawing.

Bioswale details are given in the diagram on page 11. Please refer to it.

6. Curb stone design details is not provided.

Instead of curbstone, masonry solid blocks are to be used, details given in the drawing on page 11

7. Vent Structure detail drawing is not provided.

It is not required. Steel grating will act as vents

8. Checker plate covers (steel grating) for sump well and valve chamber details is not provided.

Check plate details are provided in Page 10 of the drawing.

9. Feydhoo roads are asphalt finished. Is it our scope to cut asphalt and again repair asphalt roads after work is completed.

Yes.

10. Feydhoo old revetment is buried in the reclaimed area and the sea outfall will be passing this revetment. Normal SK 50 excavator used to do excavation for the scopes in the bid, will not be suitable to remove the rock revetment, if required to remove it. I think you must inform this to all bidders

Contractor shall assess the site conditions before preparing the BOQ.



[Handwritten signature]