

Clarification 1- Construction of Mosque at Hdh. Hanimaadhoo

1	SS pipe railing for ground floor stairs	same as Ramps details in AR14.
2	Door Schedule	included in AR19 D&W Schedule 01
3	Window Schedule (Only available W3 & W4 Details)	W1 and W2 included in AR19 D&W Schedule 01
4	Arch Pattern 3 Details	as provided in AR05 Elevations E1 E2 main entrance
5	False canopy for rainwater discharge down pipe	downpipes only connected to roof gutters. False canopies are only used above arches and do not require discharge downpipes.
6	Sound Cupboard	contractor may propose flatpack cupboard for sound room
7	Masjid Name Board	to be placed on wall above front arch
8	Calligraphy Board 2m x 4m	Wood embossed or engraved board in Mihrab Area
9	Calligraphy Board 1.5m x 4m	Wood embossed or engraved board in Prayer area
10	Fire Fighting Drawing	No drawing provided. Supply and install fire extinguishers and blankets at strategic locations to cater for any fire incident.
11	Minaret GI Ladder	contractor may propose to supply pre-fab ladders or fabricate bolted or welded GI pipes on site. Should have safe load bearing for 150kg.
12	Prefabricated Dome for Minaret	please omit 5.3 (1) as there should not be a pre-fabricated dome for minaret.
13	Minaret Door Schedule	door incorrectly labelled as D1 in AR09 Minaret Details1. It should be D5 as provided in AR19 D&W Schedule 01. D5 is 2150 x 700mm.
14	Minaret MEP drawing	included in LT01 Lighting Layout and PO01 Power Layout
15	Items not included in the BOQ PA system Boundary Wall -	- included in 12.5 Minaret BOQ - add following: 16.2.5.1 Prefab wall panels as shown in drawings and renders 16.2.5.2 Exterior plastering 16.2.5.3 Exterior textured paint
16	Pavement Floor	58sqm paving area (800L x 400W x 300Dmm blocks) near front entrance and 2x 11sqm areas (400mm side hexagonal blocks x 300mm thick) near minaret
17	Planter Box	half walls and planters 450mm height
18	Half Wall in Passage area	ditto
19	Landscape	contractors to include provision for landscaping - add following: 16.2.6.1 Landscaping
20	Please clarify the Arch materials?	Arches should be made of concrete
21	Please provide Canopy details. There is no details in the available drawing	only canopy above arches as provided in AR22 Arc Details 2
22	Please provide Solar panel Installation method and Connection Layout	Contractors should provide supplier drawings and specifications for consultants approval



23	Do we need to include Exterior Decorative elements for Prayer hall and Minaret? If needed please provide the details drawing with materials spec?	Please refer to drawings and renders provided.
24	What is the brand we want to consider for Main panel board, Distribution Board & Breakers	As stated in the specifications electrical fittings should be ABB or equivalent grade.
25	Please clarify the availability of material storage with in site premises	Only Material storage space can be arranged within the site or nearby site.
26	Can we use manufacture sand for concrete and masonry work?	It should be river sand and aggregate for all works
27	Can we use White sand for Block making ?	It should be river sand and aggregate for all works

