

Ministry of Finance and Treasury

Ameenee Magu, Male', Republic of Maldives Telephone: (960) 334 9266, Fax: (960) 332 0706 وبرستام مَدُّرُ وِثَمَّتُ مُمَنَّ عُمَدُهُ مُورِدُدُ ، دُوْ، بِرَوْرِمُدُغُ

AMENDMENT 1

No:	TES/2017/V	W-15
Project:	Health Cent	tre Extension (Finishing work) - GA.Kanduhulhudhoo
Issued Date	10 th April 2017, Monday	
352 525~ No. of Pages: -01	Boq: -00	Drawings: -00

وِهُ رَمُرَمُوهُ وِ وَسَعُوْتُ ۚ يَرِمُرُمُوهُ وِ مُنْ رَمُرَمُوهُ وَ مُنْ مُرَمُوهُ وَمُرَمُوهُ وَمُرَمُوهُ وَاللَّهِ وَاللَّهِ وَاللَّهِ وَاللَّهُ وَاللَّالِمُ وَاللَّهُ وَاللّلَّالِي وَاللَّهُ وَاللَّهُ وَاللَّهُ وَاللَّهُ وَاللَّهُ وَاللّلَّالِي وَاللَّهُ وَاللَّهُ وَاللَّهُ وَاللَّهُ وَاللَّهُ وَاللّلَّالِي وَاللَّهُ وَاللَّهُ وَاللَّهُ وَاللَّهُ وَاللَّهُ وَاللّالِي وَاللَّهُ و

- > Clarifications are attached to this Amendment.
- > The bidder may submit bid security or bid guarantee which has been issued not earlier than 14 days prior to bid submission date (18th April 2017).



The <u>Bid Opening</u> for the project will be held on <u>Tuesday</u>, 18th April 2017, 11:00hrs at National Tender and Project Monitoring section of Ministry of Finance and Treasury (5th floor, Treasury building)

Name: Ahmed Mujuthaba Signature:



Ministry of Finance and Treasury National Tender and Project Monitoring

Attachment of Amendment 1

Clarifications for:

Health Centre Extension (Finishing work) - Ga.Kanduhulhudhoo (TES/2016/W-015)

Query: 1

Bill No: 04, Masonry and plastering

What is the Plastering Thickness we have to provide in site? Whether it is 18mm or 20mm. Please conform it.

Answer: External and internal plastering thickness is 20mm.

It is mentioned only Desalinated water should be used for all purposes. If so is there any source available within the site or nearby location. Please give details.

Answer: Drinking quality water to be used for Plastering.

Query: 2

Bill No: 05, Roofing

Regarding Rain water Down Pipes there is a difference in Quantity between BOQ and Drawing. In BOQ, 8 Pipes mentioned but 11 pipes shown in drawing. What we have to follow? Please clarify it.

Answer: Please follow the drawing

Query: 3

Bill No: 06, Doors and Windows

Regarding Doors D3 & D4 there is a difference in Quantity between BOQ and drawing. What we have to follow? Please advice in it.

Answer: Please follow the drawing.

No details of Door D5 given in Drawing. Need the details.

Answer: D5 door is timber frame with decorative timber panel.



85,

E-Mail: tender@finance.gov.mv

Regarding Window W1 there is Quantity difference between BOQ and Drawing. Please advice what to follow.

Answer: Please follow the drawing.

Regarding Window Curtains for W1 there is Quantity difference between BOQ and Drawing. Please advice what to follow.

Answer: Please follow the drawing.

No separate drawing for Nurse Station Counters. Whether we have to use the same size of Registration Counter for Nurse Station Counter also or not. Please confirm it.

Answer: Nurse station counter design is same as registration counter.

Query 04:

Bill No: 07, Tiling

Regarding Wall Finish, ward area tiling should be done for 2.4m height from FFL, but the height of wall between ward and waiting area corridor is 1.80m only as mentioned in floor plan. Can we do for 1.80m height tiling in this wall and all other 3 sides tiling can be done for 2.4m height? We need clarification about it.

Answer: Ward area wall height is 2.4 meter except low height, low wall area wall tile height is 1.8Meter.

Query 05

Bill No: 10, Electrical Installations

Regarding Ceiling Fan there is Quantity difference between BOQ and Drawing. Please advice what to follow.

Answer: Please follow the drawing.

Regarding 2.5Sq.mm cabling to 1*13 Amp Power Points there is Quantity difference between BOQ and Drawing. Please advice what to follow.

Answer: Please follow the drawing.

Regarding 2.5Sq.mm cabling to Lights and Fan there is Quantity difference between BOQ and Drawing. Please advice what to follow.

Answer: Please follow the drawing.

Phone: 3349115 3349191

Regarding Fan Control there is Quantity difference between BOQ and Drawing. Please advice what to follow.



E-Mail: tender@finance.gov.mv

Answer: Please follow the drawing.

Query 06

No Water Supply Layout and Waste Water Layout Detail Drawings issued. We need the same.

Answer: Contractor has to design Plumbing layout as per the BOQ.

Query 07:

Bill No: 11, Hydraulics and Drainage

Regarding Sink Cupboards, width of the Cupboard is mentioned as 600mm in BOQ and in drawing it is shown as 900mm. Please clarify the correct width to be adopted. Regarding Rain water Tank, 5000 litres Sintex tank is mentioned in BOQ but 10000 litres is given in drawing. Please clarify it.

Answer: Capacity of rain water tank is 5000 Liters.

Query 08:

Bill No: 12, Air Conditioning System

In Consultation room 3 no's of 9000 BTU ceiling cassette is mentioned in BOQ but as per electrical layout drawing it is shown as 1 no. Please clarify it.

Answer: One consultation room need to install Air condition, please include extra 2 unit to Omission bill.



80

Phone: 3349115 3349191

E-Mail: tender@finance.gov.mv