




TREATED WATER TANK & FOUNDATION PLAN



TREATED WATER TANK & FOUNDATION-ELEVATION



DETAIL-A



SECTION X-X (01)

- NOTES:-
1. ALL DIMENSIONS ARE IN MILLIMETRES AND ALL LEVELS AER IN METRES, UNLESS OTHERWISE NOTED.
 2. DRAWINGS ARE NOT TO BE SCALED. ONLY WRITTEN DIMENSIONS ARE TO BE FOLLOWED.
 3. ALL CONCRETE WORK SHALL BE DESIGN GRADE C30.
 4. BLINDING CONCRETE WORK SHALL BE GRADE C10.
 5. ALL STRUCTURE WORK SHALL CONFORM TO BS 7668. GRADE 46A/ASTMA36. ALL STRUCTURAL MEMBERS SHALL BE HOT DIP GALVANIZED AND PAINTED AS PER SPECIFICATIONS.
 6. STEEL BARS DENOTED "T" SHALL BE HYSD BARS OF GRADE 460 CONFIRMING TO BS 4449
 7. NET SBC OF 15T/SQM IS CONSIDERED IN THE DESIGN.
 8. CLEAR COVER TO REINFORCEMENT
 - a. BEAM -40mm
 - b. SLAB -25mm



VIVEK V. PAGNIS
(STRUCTURAL ENGINEER)

TENDER PURPOSE

CLIENT				MINISTRY OF ENVIRONMENT AND ENERGY MALE REPUBLIC OF MALDIVES			
PROJECT				PROVISION OF RAINWATER HARVESTING SYSTEM IN 10 ISLANDS			
REVISION				CONSULTANCY SERVICES FOR DESIGN AND SUPERVISION OF RAINWATER HARVESTING SYSTEM IN HA, UTHEEMU, HA, MULHADHOO, HA, MURADHOO, HA, ULIGAMU, HA, MAARANDHOO, HA, FILLADHOO, HDH, FINEY, HDH, KURINBI, HDH, NEYKURENDHOO, HDH, HIRIMARADHOO, MALDIVES (PACKAGE - 1)			
No.	DESCRIPTION	BY	DATE	APPR.	DRAWING TITLE		
REVISION					TYPICAL DRAWING OF TREATED WATER STORAGE TANK		
CONSULTANT				IN ASSOCIATION WITH			
SHAH TECHNICAL CONSULTANTS PVT. LTD., INDIA				DEVELOPMENT TECHNOLOGIES MALDIVES, MALDIVES			
APPROVED	CHECKED	DESIGNED	DRAWN	REVISION			
VVP	SSS	SPP	PDP	SCALE			
AS SHOWN		DATE	FEB 2018	DRAWING NUMBER		Hdh.Finey/WS/08B	
						REVISION	
						0	