



CLARIFICATION 1

1 ވަނަ ބަޔާން ފޮނުވުމަށް ފޯމު

ޕްރޮޖެކްޓްގެ ނަންބަރު Pkg. No:	PSIP/2016/T		
ޕްރޮޖެކްޓް ނެރުވި ދުވަހު Issued Date:	6 th March 2016		
ޕްރޮޖެކްޓްގެ ނަންބަރު Project:	(TES/2016/W-04) Construction of S. Hithadhoo Campus Staff office block and Student common room (TES/2016/W-05) Construction of S. Hithadhoo Magistrate Court (TES/2016/W-06) Construction of S. Hithadhoo Nooraanee School 8 classrooms (TES/2016/W-07) Construction of S. Hithadhoo school Multi-purpose hall (capacity of 500 students)		
ޕްރޮޖެކްޓް ހުށަހަޅާ ދުވަހު Deadline for submission:	14th March 2016 (1300 hrs.)		
ޕްރޮޖެކްޓްގެ ނަންބަރު No. of Pages: -03	ޕްރޮޖެކްޓްގެ ނަންބަރު BOQ: -00	ޕްރޮޖެކްޓްގެ ނަންބަރު Drawings: -00	ޕްރޮޖެކްޓްގެ ނަންބަރު Soft Copy: -00

Please include this clarification when submitting the bid.

މި ބަޔާނު ހުށަހަޅާ ފޯމުގައި ހިމެނޭ ގޮތަށް ހުށަހަޅާ ފޯމުގައި ހިމެނޭ ގޮތަށް

- Please find the below queries

Construction of S. Hithadhoo Staff Office Block and Student Common room

1. Are there any trees to cut down?

There are 5 trees and 4 coconut palms to be cut down in the area.

2. Can we make temporary accommodation at the site?

Space for material storage will be provided within the boundary. Accommodation cannot be provided as it is an ongoing university campus.

3. Can we use water from site for concrete mixing?

Desalinated water is distributed in Hithadhoo. Desalinated water can be used.

4. Can we use local sand for masonry works?

No.

5. What is the distance from the electric main DB?

It's approximately 12m from the Main panel board (Measured from outside).

(Handwritten signature)



Construction of S hithadhoo magistrate court

1. Are there any trees to cut down?

Yes, there are trees to cut and removal of plants and shrubs, and we highly recommend **NOT to remove** the huge trees as we are planning to use those for landscaping purpose.

2. Can we make temporary accommodation at the site?

Temporary accommodations is allowed, but had to remove and clear after completion

3. Can we use water from site for concrete mixing?

Water condition is to be as per Technical Specification

4. Can we use local sand for masonry works?

Use river sand for masonry works for the building is huge and local sand to be well cleaned from salt, etc.

5. What is the distance from the electric main DB?

The electric main DB is within the range of 250 meters

Construction of S. Hithadhoo Nooraanee School

1. Are there any trees to cut down?

NO Trees to cut down.

2. Can we make temporary accommodation at the site?

NO. Temporary accommodation at the site cannot be arranged.

3. Can we use water from site for concrete mixing?

Can be used if the water condition is as stated in the technical specification.

4. Can we use local sand for Masonry works?

NO. Cannot use Local Sand.

5. What is the distance from the electric main DB?

30-40 ft. approximately



Construction of S. Hithadhoo School Multipurpose hall

1. Are there any trees to cut down?

Yes. Almost 10 trees

2. Can we make temporary accommodation at the site?

NO, Temporary accommodation at the site cannot be arranged.

3. Can we use water from site for concrete mixing?

Can be used if the water condition is as stated in the technical specification.

4. Can we use local sand for masonry works?

NO

5. What is the distance from the electric main DB?

200 ft. approximately



Name: Ahmed Mujuthaba



Signature:

