



AMENDMENT 2

2 ވަނަ ބަޔާން

ނަންބަރު No:	TES/2016/W-051	
ފޮތް ނަންބަރު Project:	Reclamation of land to develop Hdh.Kulhudhufushi Airport.	
ދިވެހި Issued Date	3 rd May 2016, Tuesday	
ސަފުހާ ގެ ޖަދުވަލު No. of Pages: -02	ބޯޖު Boq: -00	ޖަހާފައިވާ ވަނަވަންތަކުގެ ޖަދުވަލު Drawings: -00

Please include this amendment when submitting the bid. ބަޔާން ދަނީ ބަލާ ދަރިވަރުންނަށް ދަންނަވާ ފޮތް.

Attached please find answers for the questions raised regarding this project with the revised Tender document.

Please be informed that the **Bid submission date** has been revised and now will be held on **12th May 2016 at 1100hrs (Thursday)** at Ministry of Finance and Treasury, Tender Evaluation Section.

<p>ނަންބަރު Name: Ahmed Mujuthaba</p>	<p>ސަފުހާ Signature: </p>
---	-------------------------------

Kulhudhuffushi Reclamation

1. What is the maximum dredging depth permitted for borrow sites?
Maximum depth allowed is 6m from mean sea level.
2. If the soil from borrow sites are not suitable for reclamation works, what alternative borrow sites are available?
Alternative site shall be proposed by the contractor from a lagoon close to Kulhudhuffushi
3. The volume of material indicated the borrow areas in the drawing does not match with the Fill volume given in the BOQ item 2.2.
If the contractor feels that the quantity is not sufficient or more, submit a separate bill for omission/addition as specified in BOQ item 2.2.1
4. We note that the borrow sites is closer than 75m from the runway centerline is this acceptable?
The area within the strip will be filled by others.
5. What's the discharge/disposal site for removed unsuitable material from the fill area?
Will be finalized a suitable location within the strip later.
6. To what depth does the peat or unsuitable material be removed from the fill areas ?
In the land area assume depth as 600- 800 mm and in lake area depends on the survey. Contractor has to bear the risk of the depth of removal of unsuitable soil from the lake.
7. Do we include the GST component in this tender ? if so do we have to include it in the rates or show it as a separate component in the BOQ summary ?
G.S.T. not required to include.
8. What shall be done to the houses over lapping the design footprint, does the contractor have to allow for any compensation ?
This item will be handled by the government as a separate issue.

Kulhudhuffushi:

REC/01/16
RWCS/01/16
BRCS/01/16

