NO.	TOP COVER LEVEL (FROM MEAN SEA LEVEL)	INVERT LEVEL (FROM MEAN SEA LEVEL)
LS-01	+1.08	-0.50
MH-101	+0.92	+0.40
MH-102	+1.08	-0.18
MH-103	+1.11	-0.38
MH-104	+1.24	-0.14
MH-105	+1.35	-0.03
MH-106	+1.49	+0.09
MH-107	+1.30	+0.34
MH-108	+1.21	+0.24
MH-109	+1.16	+0.14

NO.	TOP COVER LEVEL (FROM MEAN SEA LEVEL)	INVERT LEVEL (FROM MEAN SEA LEVEL)
LS-02	+1.93	-0.40
MH-201	+1.41	+0.49
MH-202	+1.58	+0.34
MH-203	+1.87	+0.07
MH-204	+1.68	+0.56
MH-205	+1.93	+0.40
MH-206	+1.91	+0.59
MH-207	+1.76	+0.57
MH-208	+2.04	+0.87
MH-209	+1.61	+0.41
MH-210	+1.98	+0.25
MH-211	+1.47	+0.51

NO.	TOP COVER LEVEL (FROM MEAN SEA LEVEL)	INVERT LEVEL (FROM MEAN SEA LEVEL)
LS-03	+1.25	-0.55
MH-301	+1.29	+0.64
MH-302	+1.30	+0.29
MH-303	+1.25	-0.51
MH-304	+1.09	-0.17
MH-305	+1.19	+0.08
MH-306	+1.32	+0.32
MH-307	+1.32	+0.07
MH-308	+1.30	-0.22
MH-309	+1.41	+0.04
MH-310	+1.71	+0.75
MH-311	+1.71	+0.10
MH-312	+1.39	+0.34
MH-313	+1.65	+0.59
MH-314	+1.70	+0.89
MH-315	+1.40	+0.55
MH-316	+1.47	+0.74

NO.	TOP COVER LEVEL (FROM MEAN SEA LEVEL)	INVERT LEVEL (FROM MEAN SEA LEVEL)
LS-04	+1.47	-0.62
MH-401	+1.38	+0.58
MH-402	+1.97	+0.37
MH-403	+1.45	+0.15
MH-404	+1.48	-0.14
MH-405	+1.52	-0.42
MH-406	+1.52	-0.32
MH-407	+1.52	-0.18
MH-408	+1.46	+0.13
MH-409	+1.59	+0.16
MH-410	+1.70	+0.45
MH-411	+1.79	-0.38
MH-412	+1.69	-0.32
MH-413	+1.24	-0.12
MH-414	+1.17	+0.13
MH-415	+1.24	+0.16

NO.	TOP COVER LEVEL (FROM MEAN SEA LEVEL)	INVERT LEVEL (FROM MEAN SEA LEVEL)
LS-05	+1.54	-0.55
MH-501	+1.54	+0.44
MH-502	+1.65	+0.66
MH-503	+1.85	+1.06
MH-504	+1.42	+0.78
MH-505	+1.37	+0.42
MH-506	+1.32	-0.01
MH-507	+1.32	-0.04
MH-508	+1.29	+0.07
MH-509	+1.20	+0.52
MH-510	+1.32	+0.28
MH-511	+1.38	+0.54
MH-512	+1.29	+0.51
MH-513	+1.40	+0.47
MH-514	+1.48	+0.46
MH-515	+1.52	+0.69
MH-516	+1.82	+0.98

NO.	TOP COVER LEVEL (FROM MEAN SEA LEVEL)	INVERT LEVEL (FROM MEAN SEA LEVEL)
LS-06	+1.43	-1.05
MH-601	+1.83	+0.29
MH-602	+1.80	+0.03
MH-603	+1.87	-0.55
MH-604	+1.43	-0.70
MH-605	+1.43	-0.89
MH-606	+1.32	-0.63
MH-607	+1.76	-0.54
MH-608	+1.78	-0.37
MH-609	+0.97	+0.01
MH-610	+1.01	+0.24
MH-611	+1.26	+0.01
MH-612	+1.09	-0.58
MH-613	+1.08	-0.36
MH-614	+1.77	-0.05
MH-615	+1.58	+0.26
MH-616	+1.22	+0.55
MH-617	+1.14	+0.10
MH-618	+1.32	-0.15
MH-619	+1.36	+0.06
MH-620	+1.30	+0.33
MH-621	+1.35	+0.33

NO.	TOP COVER LEVEL (FROM MEAN SEA LEVEL)	INVERT LEVEL (FROM MEAN SEA LEVEL)
LS-07	+1.81	-0.85
MH-701	+0.88	-0.11
MH-702	+0.75	-0.27
MH-703	+1.72	+0.30
MH-704	+1.79	+0.10
MH-705	+1.81	-0.12
MH-706	+1.81	-0.70
MH-707	+1.81	-0.51
MH-708	+1.81	-0.32
MH-709	+1.41	-0.11
MH-710	+1.46	+0.10
MH-711	+1.41	+0.37
MH-712	+1.32	+0.44
MH-713	+1.32	+0.26
MH-714	+1.32	+0.18
MH-715	+1.32	+0.44
MH-716	+1.36	-0.43
MH-717	+1.36	-0.23
MH-718	+1.36	-0.02
MH-719	+1.27	+0.20
MH-720	+1.27	+0.41
MH-721	+1.37	+0.37

NOTES:-

1. ALL DIMENSIONS SHOWN ARE IN MILLIMETERS (MM), UNLESS OTHERWISE SHOWN
2. ALL LEVELS SHOWN ARE IN METERS. ALL LEVELS SHOWN ARE FROM MEAN SEA LEVEL
3. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS,GENERAL NOTES AND SPECIFICATIONS.

REFERENCE DRAWINGS

SL.No	DRAWING No.	DESCRIPTION

REV.	DATE	DESCRIPTION	DRAWN	CHKD.	APPRD.
..	..	..	..	..	..
..	..	..	.	..	..
..	..	..	..	..	..
..	..	..	..	..	..
0	15-09-'15	DETAILED DESIGN SUBMISSION	JP	SS	MA

REVISION

CLIENT

MINISTRY OF ENVIRONMENT & ENERGY
REPUBLIC OF MALDIVES

CONSULTANT: استشاري

مكتب الحبشى للاستشارات الهندسية
Al-Habshi Consultants Office
Tel.: 2430103 / 2433131 - Fax : 2431136
P.O.Box 27154 Safat 13132 - Kuwait

PROJECT:
Provision of Water Supply Facilities in 04 islands and Sewerage Facilities in 05 islands -
GDH.Gadhdhoo Island - Republic of Maldives

DRAWING TITTLE:
MANHOLE SCHEDULE
GDH.GADHDHOO ISLAND

DESIGNED	DRAWN	CHECKED	APPROVED	SCALE	DATE
SK	ST	SS	MA	AS SHOWN	15-09-'15

PROJECT No.	SHEET No.	DRAWING No.
K-619	1 OF 1	GG-SW-103
REV. No.	0	

Copyright © 2015 by Al-Habshi Consultants Office